

PLANTING SCHEDULE

QTY	KEY	COMMON NAME	BOTANICAL NAME	SIZE	MTHD	REMARKS
7	ASH	ASH, FALL GOLD	FRAXINUS NIGRA FALL GOLD	2.5"	B&B	OVERSTORY TREES; 25% TO EXCEED MIN. SIZE REQUIREMENTS
26	MPL	MAPLE, EMERALD	ACER PLATANOIDES PSEUD	2.5"	B&B	
2	OAK	OAK, SWAMP WHITE	QUERCUS BICOLOR	2.5"	B&B	
6	WW	WILLOW, WEEPING	SALIX CASCADE	2 1/2"	BR	
17	NP	PINE, NORWAY	PINUS RESINOSA	6' HT.	B&B	CONIFEROUS TREES; 25% TO EXCEED MIN. SIZE REQUIREMENTS
12	SP	PINE, SCOTCH	PINUS SYLVESTRIS	6' HT.	B&B	
17	AC	ADAMS CRAB	MALUS ADAMS	2"	B&B	ORNAMENTAL TREES; 25% TO EXCEED MIN. SIZE REQUIREMENTS
13	PSC	PINK SPIRES CRAB	MALUS PINK SPIRES	2"	B&B	
10	CL	CHINESE LILAC	SYRINGA CHINENSIS	#3	CONT.	7' O.C. STAGGERED
14	CRD	RED TWIGGED DOGWOOD, CARDINAL	CORNUS STOLONIFERA BAILEY CARDINAL	#5	CONT.	
44	RSA	RED TWIGGED DOGWOOD, ISANTI	CORNUS STOLONIFERA BAILEY ISANTI	#5	CONT.	8' - 10' APART, PLANT ON DIAGONAL SIDE
51	GLS	GRO-LOW SUMAC	RHUS GRO-LOW	#5	CONT.	
57	AJ	ARCADIA JUNIPER	JUNIPERUS SABINA ARCADIA	#5	CONT.	5' O.C.
10		EXISTING OVERSTORY TREES AT NORTHEAST CORNER OF SITE. VERIFY SPECIES AND SIZE WITH CIVIL DRAWINGS.				

LANDSCAPE NOTES:
1. SOD ALL DISTURBED AREAS. SOD TO BE PLACED OVER 4" OF BLACK DIRT CONTAINING NO MORE THAN 35% SAND. SOD IS TO BE PLACED TO THE EDGE OF THE ROADWAYS.
2. UNDERGROUND IRRIGATION SYSTEM TO BE PROVIDED FOR ALL LANDSCAPED AREAS.
3. PROVIDE ROCK IN ALL SHRUB PLANTING AREAS. ROCK TO ENCOMPASS SHRUBS 3" DEPTH.
4. VERIFY LOCATIONS OF ANNUAL BEDS ALONG BUILDINGS WITH CONTRACTOR.

LANDSCAPING CALCULATIONS

TOTAL SITE REQUIREMENTS FOR 3,049 LINEAL FEET OF SITE PERIMETER OR 42,683 SQUARE FEET OF BUILDING (INCREASE 1.5 TIMES FOR H.O.D.):
- (1) OVERSTORY DECIDUOUS SHADE TREE FOR EVERY 100 FEET OF SITE PERIMETER 3,049 FEET/100 FEET = 30.49; 30 OVERSTORY TREES (x 1.5) = 45 TOTAL
- (1) CONIFEROUS TREE FOR EVERY 2,000 SQUARE FEET OF BUILDING 42,683 S.F./2,000 S.F. = 21.34; 21 CONIFEROUS TREES (x 1.5) = 32 TOTAL
- (1) UNDERSTORY SHRUB FOR EVERY 300 SQUARE FEET OF BUILDING 42,683 S.F./300 S.F. = 142.27; 142 SHRUBS (x 1.5) = 213 TOTAL
- (1) ORNAMENTAL TREE FOR EVERY 5,000 SQUARE FEET OF BUILDING

Proposed Development
NAPLES MARKETPLACE
Blaine, Minnesota

Landscape Architect: D. YOUNG
Drawn By: ECD
Checked By: LML
Revisions

08.10.04	CITY SUBMITTAL
10.12.04	REVISED DESIGN
06.28.05	CITY SUBMITTAL
01.15.06	CITY COMMENTS
04.17.06	ISSUED

MASTER LANDSCAPE PLAN, NOTES & DETAILS

Sheet Number

ML1

Project No. 040507-1